

## **Release Notes for DrayTek VigorAP 802 (UK/Ireland)**

Firmware Version	1.3.3
Release Type	<b>Regular</b> – Upgrade recommended when convenient
Release Date	31 <sup>st</sup> January 2020
Build Date	20 <sup>th</sup> December 2019
Revision	11374
Applicable Models	VigorAP 802
Locale	UK Only

### **New Features**

1. Range Extender mode supports connection with different channels

### **Improvements**

1. Vigor router APM compatibility updated
2. Mesh node management by VigorACS server improved
3. Improved mechanism of deleting individual MAC addresses from [Wireless LAN]> [Access Control]

### **Known Issues**

(none)

---

## Firmware File Types

The file name of the firmware controls which upgrade type is performed.

If the file name is unchanged (e.g. `xxxx.all`) then the upgrade will just upgrade the firmware, whereas renaming the firmware to a `.rst` extension will wipe all settings back to factory defaults when upgrading the firmware.

## Upgrade Instructions

It is recommended that you take a configuration backup prior to upgrading the firmware. This can be done from the AP's system maintenance menu.

To upgrade firmware, select '*firmware upgrade*' from the AP's system maintenance menu and select the correct file. The access point will perform the upgrade and automatically reboot once this completes.



## Manual Upgrade

If you cannot access the AP's menu, you can put the AP into 'TFTP' mode by holding the FACTORY RESET button whilst turning the unit on and then use the Firmware Utility. That will enable TFTP mode. TFTP mode is indicated by all LEDs flashing. This mode will also be automatically enabled by the router if there is a firmware/settings abnormality. Upgrading from the web interface is easier.

---

Firmware Version	1.3.2
Release Type	<b>Regular</b> – Upgrade recommended when convenient
Release Date	11 <sup>th</sup> November 2019
Build Date	17 <sup>th</sup> October 2019
Revision	11152
Applicable Models	VigorAP 802
Locale	UK Only

### **New Features**

1. Multi-SSID (VLAN) over Mesh support added

### **Improvements**

1. Device Object added and integrated with WLAN access control & schedule
2. Advanced Config Sync for Mesh networks added for Roaming, Band Steering, Access Control and other advanced AP configuration settings
3. Some mobile devices could not receive a DHCP IP address upon reconnecting to the VigorAP in some scenarios
4. Wireless Station List enhanced with new layout and features
5. Wireless signal strength of Mesh Root in Mesh Status added
6. Uplink LED would remain on after Mesh synchronization
7. The Dashboard displayed incorrect signal status in Range Extender mode

### **Known Issues**

(none)

Firmware Version	1.3.1.1
Release Type	<b>Regular</b> – Upgrade recommended when convenient
Release Date	6 <sup>th</sup> November 2019
Build Date	20 <sup>th</sup> September 2019
Revision	11041
Applicable Models	VigorAP 802
Locale	UK Only

### **New Features**

(None)

### **Improvements**

1. Improved memory management
2. The VigorAP 802 could take longer than expected to start up in some scenarios

### **Known Issues**

1. Multi-SSID over Mesh is not supported in this firmware version.  
The feature will be available in the 1.3.2 firmware release.

Firmware Version	1.3.1
Release Type	<b>Initial Release</b>
Release Date	18 <sup>th</sup> September 2019
Build Date	27 <sup>th</sup> May 2019
Revision	10952
Applicable Models	VigorAP 802
Locale	UK Only

### **First Firmware Release for this model**

#### **Known Issues**

1. Multi-SSID over Mesh is not supported in this firmware version.  
The feature will be available in the 1.3.2 firmware release.

**[END OF FILE]**