

Release Notes for DrayTek VigorAP 1060c (UK/Ireland)

| | |
|-------------------|---|
| Firmware Version | 1.4.9 (Formal Release) |
| Release Type | Critical – Upgrade recommended immediately |
| Release Date | 27 th April 2023 |
| Build Date | 21 st March 2023 |
| Revision | g1572_0c594a29d9 |
| Applicable Models | VigorAP 1060c |
| Locale | UK Only |

New Features

(none)

Improvements

1. Improved WebGUI security (CVE-2019-16645)
2. Rogue IP detection improvements

Known Issues

(none)


Firmware File Types

The file name of the firmware controls which upgrade type is performed. If the file name is unchanged (e.g. `xxxx.all`) then the upgrade will just upgrade the firmware, whereas renaming the firmware to a `.rst` extension will wipe all settings back to factory defaults when upgrading the firmware.

Upgrade Instructions

It is recommended that you take a configuration backup prior to upgrading the firmware. This can be done from the AP's system maintenance menu.

To upgrade firmware, select '*firmware upgrade*' from the AP's system maintenance menu and select the correct file. The access point will perform the upgrade and automatically reboot once this completes.



Manual Upgrade

If you cannot access the AP's menu, you can put the AP into 'TFTP' mode by holding the FACTORY RESET button whilst turning the unit on and then use the Firmware Utility. That will enable TFTP mode. TFTP mode is indicated by all LEDs flashing. This mode will also be automatically enabled by the router if there is a firmware/settings abnormality. Upgrading from the web interface is easier.

| | |
|-------------------|--|
| Firmware Version | 1.4.8 (Formal Release) |
| Release Type | Regular – Upgrade recommended when convenient |
| Release Date | 10 th February 2023 |
| Build Date | 9 th January 2023 |
| Revision | g1541_5b38c5dfda |
| Applicable Models | VigorAP 1060c |
| Locale | UK Only |

New Features

1. Event Alert feature added into [**Diagnostics**] > [**Alert Event**]
2. WLAN security supports WPA2 PPSK mode

Improvements

1. Security mode could not be selected for SSID 8, Wireless LAN (2.4 GHz)

Known Issues

(none)

| | |
|-------------------|--|
| Firmware Version | 1.4.7 (Formal Release) |
| Release Type | Regular – Upgrade recommended when convenient |
| Release Date | 23 rd September 2022 |
| Build Date | 19 th August 2022 |
| Revision | g1470_d3740661b8 |
| Applicable Models | VigorAP 1060c |
| Locale | UK Only |

New Features

(none)

Improvements

1. Improvements to the web security

Known Issues

(none)

| | |
|-------------------|--|
| Firmware Version | 1.4.6 (Formal Release) |
| Release Type | Regular – Upgrade recommended when convenient |
| Release Date | 12 th July 2022 |
| Build Date | 07 th July 2022 |
| Revision | g1427 |
| Applicable Models | VigorAP 1060c |
| Locale | UK Only |

New Features

(none)

Improvements

1. Updated HTTPS mechanism to address the CVE-2022-0778 (OpenSSL)
2. A note added regarding importing the MAC Address device object list from CSV: .csv files should **not** contain Carriage Return “\r” and any extra space
3. VigorAP could not fully connect to VigorACS due to AuthKey issue
4. The Range Extender mode did not work after restarting the access point
5. Wireless clients connected to different SSIDs on the same radio band could not communicate with each other
6. Improvements to the wireless connection rate for the 2.4GHz 11b+11g+11n+11ax mode
7. Vigor router APM would not work when upgrading the firmware of the VigorAP from 1.4.3 to 1.4.4

Known Issues

(none)

| | |
|-------------------|--|
| Firmware Version | 1.4.5 (Formal Release) |
| Release Type | Regular – Upgrade recommended when convenient |
| Release Date | 20 th April 2022 |
| Build Date | 11 th March 2022 |
| Revision | g1340_600a69b11a |
| Applicable Models | VigorAP 1060c |
| Locale | UK Only |

New Features

1. Support for CLI AP Management over SSH

Improvements

1. 802.11ax and 160MHz on APM WLAN Profile is now supported
2. The default setting for 2.4GHz channel selection is now 'Auto select'
3. Notification of Management VLAN not being compatible with Mesh added to GUI
4. The schedule status indicator would always show grey if Daylight Saving was enabled
5. The [Objects Setting] > [Device Object] page would not display properly if apostrophe was used for one of the object names
6. When using the "&" special character in admin password, GUI won't allow to access the AP

Known Issues

(none)

| | |
|-------------------|--|
| Firmware Version | 1.4.4 (Formal Release) |
| Release Type | Regular – Upgrade recommended when convenient |
| Release Date | 16 th December 2021 |
| Build Date | 05 th November 2021 |
| Revision | g1085_3a1a17291 |
| Applicable Models | VigorAP 1060c |
| Locale | UK Only |

New Features

1. [Monitor Radio] > [Monitor Setup] allows to select the radio channels, and includes the Tool section (Network Monitor, Packet Capture) and WIDS (Wireless Intrusion Detection System)

Improvements

1. Improve the WebGUI security
2. [Wireless LAN] > [Station List] and [Dashboard] could not correctly display statistics for throughput or number of clients connected
3. Improved wording of security warning displayed when “Fast Roaming (WPA2 Enterprise)” is enabled

Known Issues

(none)

| | |
|-------------------|--|
| Firmware Version | 1.4.3 (Formal Release) |
| Release Type | Regular – Upgrade recommended when convenient |
| Release Date | 11 th August 2021 |
| Build Date | 02 nd July 2021 |
| Revision | g610_a0ed27bbe9 |
| Applicable Models | VigorAP 1060c |
| Locale | UK Only |

New Features

(none)

Improvements

1. Updated wireless chipset drivers to resolve CVE-2020-26139 to CVE-2020-26145, CVE-2020-24586 to CVE-2020-24588

Known Issues

(none)

| | |
|-------------------|--|
| Firmware Version | 1.4.2 (Formal Release) |
| Release Type | Regular – Upgrade recommended when convenient |
| Release Date | 25 th June 2021 |
| Build Date | 01 st June 2021 |
| Revision | g585_dafe477 |
| Applicable Models | VigorAP 1060c |
| Locale | UK Only |

New Features

(none)

Improvements

1. Mesh network stability improvements

Known Issues

(none)

| | |
|-------------------|--|
| Firmware Version | 1.4.1 (Formal Release) |
| Release Type | Regular – Upgrade recommended when convenient |
| Release Date | 14 th May 2021 |
| Build Date | 29 th March 2021 |
| Revision | g522_c8668ce |
| Applicable Models | VigorAP 1060c |
| Locale | UK Only |

New Features

1. Support for IEEE 802.11r roaming protocol

Improvements

1. Improved the web page display of [Monitor Radio] > [Dashboard]
2. The comment description of the [Access Control] > [MAC Address Filter] pages for WLAN 2.4G and 5G is made consistent
3. In some circumstances AP in mesh node mode could disconnect from the root
4. Login Page did not appear properly in Internet Explorer browser
5. A mesh-related message was shown in the wrong Syslog tab
6. WLAN profile could not be configured via VigorConnect
7. TR-069 parameters updated for WLAN 2.4G advanced settings

Known Issues

(none)

| | |
|-------------------|--------------------------------|
| Firmware Version | 1.4.0 (Formal Release) |
| Release Type | Initial Release |
| Release Date | 26 th April 2021 |
| Build Date | 18 th February 2021 |
| Revision | g471_16c3b5b |
| Applicable Models | VigorAP 1060c |
| Locale | UK Only |

First Firmware Release for this model

Known Issues

(None)

[END OF FILE]